

Cryogenic Systems for the APS Upgrade

Joel Fuerst ASD/MD

ASD Seminar 30JAN2012



Outline

- Helium usage (1)
- Safety
- Loads/temperatures/locations
- Methods of refrigeration
 - SCU: cryocoolers
 - SPX: expansion engine refrigeration
- Support for SPX R&D
- Helium usage (2)
- Summary



Fermilab uses some helium - 1981 (1)



Fermilab uses some helium - 1981 (2)



Fermilab uses some helium - 1981 (3)



5

Fermilab uses some helium - 1981 (4)



Fermilab uses some helium - 1981 (5)



Cryogenic Systems Safety

- ES&H-4.10 Cryogenic Liquid Safety
- ES&H-13.1 Pressure Systems Safety
- Vacuum Systems Consensus Guideline for DOE Accelerator Laboratories
- 10 CFR 851 Worker Safety and Health Program
 - 851.3(a): Pressure systems means all pressure vessels, and pressure sources including cryogenics, pneumatic, hydraulic, and vacuum.
 - Appendix A, 4. Pressure Safety:
 - (a) establish policies & procedures to ensure systems follow sound engineering principles
 - (b) ensure pressure vessels & piping systems conform to the ASME Boiler & Pressure Vessel Code and the applicable ASME B31 piping standards
 - (c) when codes are not applicable, implement measures to provide equivalent protection
- n PTSC (https://docs.anl.gov/lms/processes/safety/LABCOM-1.28)
- Training (Cryogenic Safety, ESH 145; Pressure Safety Orientation, ESH 119)
- Oxygen Deficiency Hazard (ODH) & engineered control measures
 - Environmental controls: ventilation (natural or forced), monitoring
 - Personnel controls: training, signage, barriers to entry, personal monitors, escape packs, etc. depending on hazard level



ODH Class	Fatality Rate φ [hr-		
	1]		
0	φ <1e-7		
1	1e-7≤φ<1e-5		
2	1e-5≤φ<1e-3		
3	1e-3≤φ<1e-1		
4	1e-1≤φ		

$\varphi = \sum_{i=1}^{n} P_i F_i$

FNAL example failure rate Pi: 5A. Magnet (cryogenic)

"Up to January 1999, there have been 63,000 hours of Tevatron system powered conditions. There have been 11 magnet spill events mostly, if not all, due to single-phase rupture to vacuum from an electrical fault. Then magnet "powered, unmanned " failure rate is: Tailure rate = $\frac{63000 \times 1000}{1000}$ magnets





ASD Seminar: Cryogenic Systems for the APS Upgrade

9

Heat loads/Operating temperatures

SCU (design values per device)

SPX (design values for full installation)

	Heat source	Temp [K]	Design load [W]	Installed capacity [W]
SCU	Magnet	4.3	0.7	3
	Rad shield/ beam tube	20	12	40
	Rad shield	60	86	224

SPX	Srf cavities	2.0	100	320
	Rad shield	5-8	300	500
	Rad shield	80	2000	4000 (LN2)



Cryogenic Systems Locations

SPX0: sector 5 (production SPX in sectors 5 & 7)

SCU0: sector 6



SCU: Gifford-McMahon (GM) cryocooler cycle



RDK-415D Typical Load Map (60Hz)

Sumitomo RDK-415D Performance Maps

- Upper graph shows performance envelope under various operating conditions
- Lower graph shows available 2nd stage (lowest temperature) cooling power as a function of temperature during cooldown





Bldg 314 - JAN2012



SPX Approach

- Cryoplant purchased turn-key from industry
 - Build-to-performance based on peer-reviewed APS-U spec
 - Follow established procurement strategies (JLab, FNAL, FRIB, SNS)
 - Distribution system purchased and installed by industry
 - BOE drawn from recent plant procurements (FNAL) and SME input
- Cryomodules supplied by JLab
 - Designed in collaboration with ANL, to meet ANL ES&H requirements
 - Consistent with SR constraints
 - Cryomodule and distribution system heat loads set cryoplant performance spec
- Cryosystems for R&D phase
 - JLab contributions
 - ANL-designed components

Reviews will follow SCU model ASD Seminar: Cryogenic Systems for the APS Upgrade

SPX: Expansion Engine Refrigeration

Basic Claude cycle: n

ID Fueret



30 IAN2012



Existing SPX-sized cryoplants

- ELBE (Dresden-Rossendorf)
 - Electron Linac
 - Linde custom refrigerator operating since 1999
 - 220 W at 1.8 K

ELBE compressors, coldboxELBE compressors, coldbox

- TRIUMF (Vancouver)
 - RIB Linac (ISAC-I, II)
 - Dual Linde TCF50
 refrigerators commissioned
 2006 and 2008
 - Total 1200 W at 4.5 K



TRIUMF coldboxes & dewarTRIUMF compressor

- BESSYII (Berlin)
 - Light Source, ERL R&D
 - Linde *L70*0 liquefier: 710 L/hr
 - Linde TCF50 refrigerator: 150
 W at 4.5 K + 55 L/hr
 liquefaction







HoBiCaT test cryostat

Distribution system example: FRIB

- Transfer line multiple line, shielded, vacuum jacketed
- Feedbox connects transfer line to cryomodules



ID Fueret

30 IAN2012



PHY resonator test area: existing srf facility at ANL

- Located in bldg 203
- Part of ATLAS heavy ion accelerator
- Low-beta srf cavity development
- Two shielded, interlocked test caves
- Cryogenic support (frig, dewars)
- <2.0K capability (>50W @2.0K thanks to APS improvements)
- Very crowded, esp. for HTB tests







SPX srf cavity R&D at ANL

- [§] New infrastructure provided by APSU:
 - 2.5g/s vacuum pump needs to return to APS for SPX0 (or PHY buys us another)
 - Thermometry, liquid level, pressure instrumentation, LabView + PC
 - [§] LLRF, HLRF and associated electronics
 - New JTHX feedcan + neck insert for 24" dewar
 - S New transfer tubes as required
- R&D has 3 phases:
 - Single "bare cavity" vertical tests in modified PHY 24" LHe vessel
 - 2) Single "dressed cavity" horizontal tests in modified PHY TC2 vessel
 - ³⁾ Test of JLab Horizontal Test Bed (HTB) 2cavity module (requires 2 complete rf stations)



ARSU Semifrar: Certogenil Systems of the APS Upgrade

TC2 with PHY SSR prototype

PHY 24" ID vertical test dewar lavout



Test dewar: neck insert/JTHX feedbox

- Fabricated by Meyer Tool from ANL-supplied Pro/E model
- Designed to accommodate active cavity pumping
- JTHX sized for 2.5g/s at 1.8K: n
 - HP stream: 4.5K inlet, ~2.2K outlet, <20kPa Δ P
 - LP stream: 1.8K inlet, <100Pa ΔP
 - 450mm x 150mm x 125mm (LxWxD)



30 IAN2012 ID Fuerst

New vacuum system

- Rated for 2.5 g/s at 20 torr
- Identical to units at Fermilab





Engineering Cooldowns

- Cryosystem works
- Vacuum pump measured performance:
 - 60 W at 2.0 K (~3 g/s at 24 torr)
 - 40 W at 1.9 K
 - 25 W at 1.8 K
 - 15 W at 1.7 K





Neck Insert with Cavity

Installation complete 30NOV11

Ready for cooldown 02DEC11









Cavity test results

Mark-I Cavity (CC-B1 for SPX Project) Vertical Test at ANL 12/20/2011



Preparations for Phase 2



Phase 3 example: FNAL "A0 North" cavity test area



- Vac system alongside supply dewars
- Vacuum instulated transfer line on the wall behind

n Transfer line enters cave, divides, connects to cryostat services

Helium usage

- FNAL Tevatron era: avg. 30,000 cubic feet/day = 1200 liquid liters/day
- FNAL A0 Photoinjector (1.8 K, 500L dewar fed): 500L/day for several years before finally installing a gas recovery system
- SPX0 will be dewar fed (like the A0PI...)
 - If the heat load is 40W,
 - Then the flow rate is about 2 g/s
 - Which equals 58 L/hr
 - So a 500L dewar lasts one 8 hr shift:
 - How many shifts will it take to learn the lessons of SPX0?
 - How will these shifts be distributed, and what sort of "stand-by" can we implement when not testing?

Major Challenges and Risks

SCU:

n

n

- Verify magnet cooling scheme
- Verify heat load estimates
- Verify cryostat assembly and alignment scheme
- SPX:
 - Accurate estimate for heat loads
 - Damper thermal load management
 - Cryomodule layout/subsystem packaging
 - Alignment
 - Microphonics



Summary

- Activities are aligned with laboratory standards & policies
- SME involvement end-to-end
- Consistent review process
- Close collaboration with partner laboratories
- Active communication with cryogenics community:
 - Laboratories
 - Universities
 - Industry